

**SCHEDULE OF WORKS FOR EXECUTION OF FALSE CEILING AT 1ST & 2ND FLOOR AT H.O.**

SL NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE	AMOUNT
1	Providing and fixing of Armstrong Acoustic Board 600 x 600 butt jointed false ceiling with hidden grid suspension system as recommended by manufacturer sufficient to carry the load of false ceiling and light fixtures suspended from the 15' high existing c	sq.ft.	9250		
2	Providing and fixing of Gypboard false ceiling with proper suspension system as recommended by manufacturer sufficient to carry the load of false ceiling and light fixtures suspended from the 15' high existing celing. All supports and boards are to be of	sq.ft.	500		
3	Providing and fixing of Ornamental Gypboard false ceiling as per drawing with proper suspension system as recommended by manufacturer sufficient to carry the load of false ceiling and light fixtures suspended from the 15' high existing ceiling. All suppo	sq.ft.	500		
4	Removal of existing vertical boards and providing and fixing of Armstrong Acoustic Board 600 x 600 but jointed on the hidden grid as per direction of Engineer In-Charge	sq.ft.	500		